

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-019-20958-00-00  
Spot: NWSESW Sec/Twnshp/Rge: 10-34S-8E  
943 feet from S Section Line, 3532 feet from E Section Line  
Lease Name: LEEDY Well #: 7  
County: CHAUTAUQUA Total Vertical Depth: 2200 feet

Operator License No.: 31767  
Op Name: SEYMOUR OIL CO., INC.  
Address: 3830 NORTHSIDE DRIVE  
MACON, GA 31210

7150

Well Type: EOR UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/17/2009 8:00 AM

Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.

Proposal Rcvd. from: \_\_\_\_\_ Company: \_\_\_\_\_ Phone: \_\_\_\_\_

Proposed Plugging Method: 50' Plug at TD (2200"), 50' plug at 1000' and 550' to surface (Unauthorized injection well E-25,099)

Plugging Proposal Received By: DUANE SIMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 08/17/2009 8:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

(Well was an unauthorized injection well). Tried to perforate well but couldn't get perforating tool down hole. Washed 1" to 1150' and hit something solid. Couldn't go any deeper. Perforated at 1100' and 550'. Ran 1" into 1150' and pumped 20 sacks of cement. Pulled 1" up to 550' and circulated cement to surface inside and outside casing. Pulled 1" and topped well off. A total of 120 sacks of cement were used to plug this well. Contractor came back at later date and topped well off again.

INVOICED  
DATE 12-17-09  
INV. NO. 2010060575

RECEIVED  
KCC DISTRICT #3

OCT 20 2009  
DAS  
CHANUTE, KS

RECEIVED  
OCT 22 2009  
KCC WICHITA

Remarks: SOMETHING WAS IN HOLE AT 1100' THAT DIDN'T ALLOW US TO GET ANY DEEPER IN WELL. THIS WELL WAS AN UNAUTHORIZED INJECTION WELL. (E-25.099)

Plugged through: TBG

District: 03

Signed [Signature]  
(TECHNICIAN)