

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-00360-00-01
Spot: SWSENE Sec/Twnshp/Rge: 17-35S-7E
2756 feet from S Section Line, 911 feet from E Section Line
Lease Name: DOROTHY OWWO Well #: 4
County: COWLEY Total Vertical Depth: 2691 feet

Operator License No.: 4555
Op Name: ROADRUNNER ENERGY, INC.
Address: 7225 S 85 E AVE # 100
TULSA, OK 74133

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2190		
CIBP		2551		
SURF	8.625	100		60 SX
PROD	5.5	2659		150 (DV TOOL)

87.46

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/02/2009 8:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, INC.
Proposal Rcvd. from: DENNIS CLAY Company: ROADRUNNER ENERGY INC Phone: (918) 250-8589

Proposed Plugging Method: AS PER KCC RULES & REGS. SET CIBP @ 1900', W/3 SXS, PERFORATE @ 300', CIRCULATE CEMENT TO SURFACE

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 09/30/2009 12:30 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

6-2-2009, RIH ON WIRELINE SET CIBP @ 1900', DUMP BAILED SXS CEMENT ON TOP. CUT CASING @ 1001', 6-15-2009, MOVED IN RIGGED UP PULLING UNIT. TRIED TO PULL CASING, WOULD NOT PULL OUT OF HOLE. 6-17-2009, RIH ON WIRELINE PERFORATED SQUEEZE HOLES @ 300'. 7-24-2009, RIH W/1" TBG @ 300', COPELAND ACID & CEMENT MIXED & PUMPED 110 SXS 60/40 POZMIX 4% GEL TO SURFACE. LAYED DOWN 1" TBG, SWEDGED INTO 5.5" CASING, FINISHED PUMPING 15 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. 9-30-2009, RIH W/1" TBG ON BACK SIDE 5-1/2" CASING @ 115'. COPELAND ACID & PLUGGING MIXED & PUMPED 10 SXS 60/40 POZMIX 4% GEL TO SURFACE, RIH W/1" TBG ON INSIDE 5-1/2" CASING @ 246', COPELAND ACID & PLUGGING MIXED & PUMPED 45 SXS 60/40 POZMIX 4% GEL TO SURFACE. P & A COMPLETE 9-30-2009, 12:30 PM. COPELAND ACID & CEMENT, TICKET #'S 33799, 34282 .

Perfs:

Top	Bot	Thru	Comments
2659	2691	CSG	
2174	2190	CSG	
2160	2167	CSG	
1994	1998	CSG	
1978	1982	CSG	
1950	1958	CSG	
1904	1914	CSG	

INVOICED
DATE 12-17-09
INV. NO. 20RECEIVED 573
OCT 26 2009
KCC WICHITA

Remarks: CIBP'S SET @ 2551', & 2190', SQUEEZED ALL PERFS ABOVE 2167', RE-SET CIBP FROM 2190' @ 2300'.

Plugged through: TBG

District: 02

Signed Duane Krueger
(TECHNICIAN)