

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-23235-00-00
Spot: SESWNE Sec/Twnshp/Rge: 17-35S-7E
2817 feet from S Section Line, 1618 feet from E Section Line
Lease Name: DOROTHY Well #: 11
County: COWLEY Total Vertical Depth: 3020 feet

Operator License No.: 4555
Op Name: ROADRUNNER ENERGY, INC.
Address: 7225 S 85 E AVE # 100
TULSA, OK 74133

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2150		
CIBP		2560		
SURF	10.75	300		150 SX
PROD	7	3016		445 SX (DV TOOL)

98.15

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/02/2009 8:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, INC.
Proposal Rcvd. from: DENNIS CLAY Company: ROADRUNNER ENERGY INC Phone: (918) 250-8589

Proposed Plugging Method: AS PER KCC RULES & REGS SET CIBP @ 1920', W/3 SXS, PERFORATE @ 300', CIRCULATE CEMENT TO SURFACE.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 09/30/2009 2:30 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:
6-2-2009, RIH ON WIRELINE SET CIBP @ 1920', DUMP BAILED 3 SXS CEMENT ON TOP. PERFORATED SQUEEZE HOLES @ 300'. 7-24-2009, RIH W/1" TBG @ 300', COPELAND ACID & CEMENT MIXED & PUMPED 140 SXS 60/40 POZMIX 4% GEL TO SURFACE. LAYED DOWN 1" TBG, SWEDGED INTO 7" CASING. FINISHED PUMPING 22SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. 9-30-2009, TOPPED WELL OFF W/10 SXS DRY CEMENT. P&A COMPLETE 9-30-2009. COPELAND ACID & CEMENT, TICKET #S 33797, 34285.

Perfs:

Top	Bot	Thru	Comments
2948	2980	CSG	
2912	2934	CSG	
2884	2896	CSG	
2193	2206	CSG	
2182	2186	CSG	
2060	2068	CSG	
1970	1980	CSG	

INVOICED
DATE 12-17-09
INV. NO. 2010060573
RECEIVED
OCT 26 2009
KCC WICHITA

Remarks: CIBP'S SET @ 2150', & 2560', PERFS @ 1970-1980 SQUEEZED W/CEMENT
Plugged through: TBG

District: 02 Signed Duane Krueger (TECHNICIAN) *PPT*