

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-24045-00-00
Spot: SESENE Sec/Twnshp/Rge: 17-35S-7E
2715 feet from S Section Line, 506 feet from E Section Line
Lease Name: DOROTHY Well #: 16
County: COWLEY Total Vertical Depth: 2725 feet

Operator License No.: 4555
Op Name: ROADRUNNER ENERGY, INC.
Address: 7225 S 85 E AVE # 100
TULSA, OK 74133

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	300		175 SX
PROD	5.5	2797		200 SX

88.56

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/02/2009 8:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, INC.
Proposal Rcvd. from: DENNIS CLAY Company: ROADRUNNER ENERGY INC Phone: (918) 250-8589

Proposed Plugging Method: AS PER KCC RULES & REGS, SET CIBP @ 2125', W/3 SKS, PERFORATE @ 300', CIRCULATE CEMENT SURFACE

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 09/30/2009 1:30 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

6-2-2009. RIH ON WIRELINE SET CIBP @ 2125' DUMP BAILED 3 SXS CEMENT ON TOP. CUT CASING @ 1690'. 6-15-2009, MOVED IN RIGGED UP PULLING UNIT. TRIED TO PULL CASING, WOULD NOT PULL OUT OF HOLE. 6-17-2009, RIH ON WIRELINE PERFORATED SQUEEZE HOLES @ 300'. 7-24-2009, RIH W/1" TBG @ 300', COPELAND ACID & CEMENT MIXED & PUMPED 110 SXS 60/40 POZMIX 4% GEL TO SURFACE. LAYED DOWN 1" TBG, SWEDGED INTO 5.5" CASING, FINISHED PUMPING 15 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. 9-30-2009, RIH W/1" TBG ON BACKSIDE 5-1/2" CASING @ 30', COPELAND ACID & PLUGGING MIXED & PUMPED 5 SXS 60/40 POZMIX 4% GEL TO SURFACE, RIH W/1" TBG ON INSIDE 5-1/2" CASING @ 190', COPELAND ACID & PLUGGING MIXED & PUMPED 21 SXS 60/40 POZMIX 4% GEL TO SURFACE. P & A COMPLETE 9-30-2009. 1:30 P.M. COPELAND ACID & CEMENT, TICKET #S 33798, 34285.

Perfs:

Top	Bot	Thru	Comments
2178	2190	CSG	

RECEIVED
OCT 28 2009
KCC WICHITA

INVOICED

DATE 12-17-09
INV. NO. 2010060573

Remarks:

Plugged through: TBG

District: 02

Signed

Duane Krueger

(TECHNICIAN)

PKT