

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-23057-00-00  
Spot: NESENWSE Sec/Twnshp/Rge: 5-8S-22W  
1940 feet from S Section Line, 1400 feet from E Section Line  
Lease Name: CHALFANT C Well #: 1-5  
County: GRAHAM Total Vertical Depth: 3700 feet

Operator License No.: 3293  
Op Name: RUSSELL OIL, INC.  
Address: PO BOX 1469  
PLAINFIELD, IL 60544

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3700		
SURF	8.625	267	0	175 SX CMT. <u>120.25</u>
PC	5.5	1723		200sx
PROD	5.5	3768	0	110 SX CMT.bottom stage

Well Type: OIL UIC Docket No: 6426 Date/Time to Plug: 10/28/2009 9:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: expresswell service & supply inc  
Proposal Rcvd. from: TODD BROWN Company: RUSSELL OIL, INC. Phone: (785) 445-6270

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 500# hulls - 14 sxs gel.  
Port collar at 1798'. CIBP over Arbuckle at 3700'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/28/2009 10:15 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:  
Tied onto 5 1/2" - pumped 50 sxs cement with 200# hulls - pumped 14 sxs gel - pumped 195 sxs cement - full of cement.  
Tied onto backside - pumped 10 sxs cement - full.

Perfs:

Top	Bot	Thru	Comments
3735	3739		
3729	3731		
3700	3700		perm plug
3542	3547		
3393	3396		

**INVOICED**  
DATE 12-17-09  
INV. NO. 2010060574  
**RECEIVED**  
**OCT 30 2009**  
**KCC WICHITA**

Remarks: ALLIED CEMENTING COMPANY-TICKET #33635.  
Plugged through: CSG

District: 04 Signed [Signature] (TECHNICIAN) CM

OCT 29 2009

RUSSELL OIL  
PLAINFIELD IL 60544

5-08S-22W  
1940' FSL & 1400' FEL, SEC

#1-5 CHALFANT C

site: 3/4 N & 2-1/4 E OF HILL CITY KS	city: GRAHAM	API 15-065-23057	<table border="1"> <tr><td></td><td></td><td></td><td></td></tr> <tr><td></td><td></td><td></td><td></td></tr> <tr><td></td><td></td><td></td><td></td></tr> <tr><td></td><td></td><td></td><td></td></tr> </table>																
contr: SOUTHWIND DRILLING #1	field: HARMONY SOUTH EXT (5/8 E;																		
geol: TODD E. MORGENSTERN	INFL.D DISC)																		
fr date 04/20/2005	spd date 05/04/2005	drig comp 05/13/2005	card issued 09/26/2005	last revised 07/10/2006															

ELV: 2151 KB, 2141 GL  
 tops .....depth/datum  
 RTD .....3790 -1639  
 NO TOPS RPTD  
 LOGGED

IP status:  
 OIL, P 44 BOPD, NW, LKC 3393-3547 OA, 06/09/2005  
 INFO RELEASED: 7/10/2006 - WAS OIL WELL - TIGHT HOLE  
 CSG: 8-5/8" 268 / 200 SX (ALT 2), 5-1/2" 3768 / 110 SX, MULTI  
 STAGE COLLAR AT 1798 / 200 SX  
 COMMENT: MI & RURT 5/3/2005; TD IN ARB FOR POSS  
 SWD USE LATER  
 NO CORES  
 DSTS TAKEN - DETAILS NA  
 TRGT ZN: LKC (OIL), PTD 3700 (ARB), MICT (6/8/2005) - CO,  
 PF (ARB) 3729-3731, 3735-3739, W / 4 SPF, AC 2000 GAL  
 (15%), SWB LD, NON-COMMERCIAL, SET CIBP AT 3700, PF  
 (LANS I) 3542-3547, W / 4 SPF, AC 750 GAL (15%), SWB LD,  
 SO, PF (LANS A) 3393-3396, W / 4 SPF, AC 500 GAL (15%),  
 SWB LD, SO, NO TBG RUN, POP, IPP 44' BOPD, NW, DOFP  
 6/9/2005, COMMINGLED - NO OTHER INFO AVAILABLE

COPYRIGHT 2006  
 INDEPENDENT OIL & GAS SERVICE, INC.  
 WICHITA, KANSAS