

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-001-22087-00-00  
Spot: <sup>NW SW</sup> ~~NWSE~~ Sec/Twnshp/Rge: 36-24S-17E  
1084 feet from S Section Line, 2190 feet from E Section Line  
Lease Name: HOMER L TEATS Well #: 7  
County: ALLEN Total Vertical Depth: 823 feet

Operator License No.: 33097  
Op Name: SOUTHERN STAR CENTRAL GAS PIPE  
Address: 4700 HWY 56  
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	6.25	20	0	
PROD 2		823	0	

35.00

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/29/2009 9:30 AM  
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE WELL SERVICE, INC.  
Proposal Rcvd. from: BERNIE RUCKER Company: SSOUTHERN STAR Phone: (720) 852-5000

Proposed  
Plugging  
Method:

THIS WELL CONSISTED OF 2" CASING TO 823' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP.  
THE PLUGGING PROPOSAL WAS TO CIRCULATE THE 2" CASING FULL OF CEMENT.

Plugging Proposal Received By: CLAYTON TITEL Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 09/29/2009 10:30 AM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

1" PIPE WAS RAN INTO THE 2" CASING TO 823'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT SURFACE. THE 1" PIPE WAS REMOVED. THE WELL WAS SQUEEZED TO 500PSI AND SHUT IN.

Perfs:

RECEIVED  
KCC DISTRICT #3

OCT 21 2009 CPT

CHANUTE, KS

INVOICED  
DATE 12-17-09  
INV. NO. 2010060576

RECEIVED  
KANSAS CORPORATION COMMISSION  
OCT 26 2009  
CONSERVATION DIVISION  
WICHITA, KS

Remarks:

Plugged through: TBG

District: 03

Signed

Clayton P. Titel

(TECHNICIAN)

*PCT*