

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-001-22242-00-00
Spot: nenwnwse Sec/Twnshp/Rge: 36-24S-17E
2483 feet from S Section Line, 2267 feet from E Section Line
Lease Name: HOMER L TEATS Well #: 8
County: ALLEN Total Vertical Depth: 816 feet

Operator License No.: 33097
Op Name: SOUTHERN STAR CENTRAL GAS PIPE
Address: 4700 HWY 56
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	6.25	20	0	
PROD 2		816	0	

35.00

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/28/2009 2:15 PM
Plug Co. License No.: 32006 ³⁴⁰⁵⁹ Plug Co. Name: HURRICANE WELL SERVICE, INC.
Proposal Rcvd. from: BERNIE RUTGERS Company: SOUTHERN STAR CENTRAL PIPEL Phone: (270) 852-5000

Proposed Plugging Method: THIS WELL COONSISTED OF 2" CASING TO 816' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO CIRCULATE THE CASING FULL OF CEMENT.

Plugging Proposal Received By: CLAYTON TITEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/28/2009 3:30 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

1" PIPE WAS RAN INTO THE 2" CASING TO 816' CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRUCLATED FROM THE CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFAE. THE WELL WAS SHUT IN AND SQUEEZED TO 500 PSI.

Perfs:

INVOICED
DATE 12-17-09
INV. NO. 2010060576

RECEIVED
KCC DISTRICT #3

OCT 14 2009

CPT

CHANUTE, KS

RECEIVED
OCT 22 2009
KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed Clayton P. Titel
(TECHNICIAN)

PPT