

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-001-22479-00-00
Spot: NWNWSE Sec/Twnshp/Rge: 36-24S-17E
2121 feet from S Section Line, 2190 feet from E Section Line
Lease Name: HOMER L TEATS Well #: 10
County: ALLEN Total Vertical Depth: 814 feet

Operator License No.: 33097
Op Name: SOUTHERN STAR CENTRAL GAS PIPE
Address: 4700 HWY 56
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	6.25	20	0	
PROD 2		814	0	

35.00

Well Type: OIL UIC Docket No: 34059 Date/Time to Plug: 09/28/2009 11:30 AM
Plug Co. License No.: 32006 Plug Co. Name: HURRICANE WELL SERVICE, INC.
Proposal Rcvd. from: BERNIE RUTGER Company: SOUTHERN STAR CENTRAL GAS P Phone: (270) 852-5000

Proposed Plugging Method: THIS WELL CONSISTED OF 2" CASING TO 814' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO CIRCULATE THE 2" CASING FULL OF CEMENT.

Plugging Proposal Received By: CLAYTON TITEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/28/2009 1:30 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

1" PIPE WAS RAN INTO THE 2" CASING TO 814'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE. THE WELL WAS THEN SHUT AND SQUEEZED TO 700 P.S.I..

Perfs:

INVOICED
DATE 12-17-09
INV. NO. 2010060576

RECEIVED
KCC DISTRICT #3

OCT 14 2009 CPT

CHANUTE, KS

RECEIVED
OCT 22 2009
KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed

Clayton P. Titel
(TECHNICIAN)