

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-097-20861-00-00  
Spot: SENW Sec/Twnshp/Rge: 26-30S-18W  
3300 feet from S Section Line, 3300 feet from E Section Line  
Lease Name: UNRUH UNIT-ALTON UNRUH Well #: 3  
County: KIOWA Total Vertical Depth: 5092 feet

Operator License No.: 5030  
Op Name: VESS OIL CORPORATION  
Address: 1700 WATERFRONT PKWY BLDG 500  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5004		
SURF	8.625	528		WITH 400 SX CMT
PROD	5.5	5057	3230	WITH 250 SX CMT

165.49

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/16/2009 9:30 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 4810' & 5 SX CMT. LOAD HOLE WITH GEL & 50 SX CMT AT 1200'. PLUG AT 540' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT  
Date/Time Plugging Completed: 10/16/2009 11:30 AM

WitnessType: COMPLETE (100%)  
KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

SAND TO 4800' WITH 5 SX CMT. 1ST PLUG AT 1210' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 540' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 12 SX CMT. CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
5057	5092	OH	MISS OH
4867	4884		MARMATON

**INVOICED**  
DATE 12-17-09  
INV. NO. 2010060580

RECEIVED  
KANSAS CORPORATION COMMISSION

OCT 27 2009

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: CSG

CONSERVATION DIVISION  
WICHITA, KS

District: 01

RECEIVED  
OCT 19 2009  
KCC DODGE CITY

Signed Jerry W. Stapleton  
PIRZZ (TECHNICIAN)

Form 622