

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-083-21611-00-00
Spot: SENWSESE Sec/Twnshp/Rge: 24-24S-26W
800 feet from S Section Line, 720 feet from E Section Line
Lease Name: HARMS Well #: 1-24
County: HODGEMAN Total Vertical Depth: 5100 feet

Operator License No.: 5004
Op Name: VINCENT OIL CORPORATION
Address: 155 N MARKET STE 700
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	312		

165.75

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 10/17/2009 3:30 PM
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.
Proposal Rcvd. from: MIKE GODFREY Company: DUKE DRILLING CO., INC. Phone: (316) 267-1331

Proposed Plugging Method: 1ST PLUG AT 1780' WITH 50 SX CMT. 2ND PLUG AT 1080' WITH 80 SX CMT. 3RD PLUG AT 570' WITH 40 SX CMT. 4TH PLUG AT 330' WITH 40 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: STEVE DURRANT Witness Type: NONE
Date/Time Plugging Completed: 10/17/2009 6:15 PM KCC Agent: STEVE DURRANT

Actual Plugging Report:

1ST PLUG AT 1780' WITH 50 SX CMT. 2ND PLUG AT 1080' WITH 80 SX CMT. 3RD PLUG AT 570' WITH 40 SX CMT. 4TH PLUG AT 330' WITH 40 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Perfs:

INVOICED
DATE 12-17-09
INV. NO. 2010060581

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

RECEIVED
KANSAS CORPORATION COMMISSION

OCT 27 2009

CONSERVATION DIVISION
WICHITA, KS

District: 01

Signed Steve Durrant
(TECHNICIAN)

RECEIVED

OCT 19 2009

KCC DODGE CITY