

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-22246-00-00
Spot: SWSWNWSE Sec/Twnshp/Rge: 2-27S-13W
1590 feet from S Section Line, 2480 feet from E Section Line
Lease Name: S AND S UNIT Well #: 3
County: PRATT Total Vertical Depth: 4450 feet

Operator License No.: 33810
Op Name: WALCHER OIL, LC
Address: 150 N MAIN STE 809
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	10.75	398		WITH 275 SX CMT
PROD	5.5	4450	3230	WITH 160 SX CMT 144.63

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 10/07/2009 1:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND BACK BOTTOM TO 3720' & PUT 5 SX CMT ON TOP OF SAND BRIDGE. PLUG AT 750' WITH 20 SX GEL & 50 SX CMT. PLUG AT 420' WITH 80 SX CMT. PLUG AT 40' WITH 30 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/16/2009 11:01 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PUMPED DOWN 5 1/2" CASING WITH 200# HULLS & 35 SX CMT. TAG TOC @ 3675'. 1ST PLUG AT 750' WITH 20 SX GEL & 50 SX CMT. NO CIRCULATION. HOLE WOULD NOT LOAD. SHUT DOWN. 10/12/09: TAG TOC @ 835'. RUN CASING BACK TO 750' & PUMPED 53 SX GEL W/750# HULLS. SPOT 50 SX CMT W/3% CC. HAD NO RETURNS. LET CMT SET 3 HOURS. TAG TOC @ 830'. RUN CASING BACK TO 750'. PUMPED 28 SX GEL & 50 SX CMT W/3% CC & 250# HULLS. NO RETURNS. SHUT DOWN. 10/13/09: TAG TOC @ 830'. RUN CSG BACK TO 750'. PUMPED 25 BBL DRILLING MUD W/400# HULLS. HOLE LOADED. PUMP TRUCK BROKE DOWN. 10/16/09: HOLE STAYED FULL. SPOT 50 SX CMT AT 750'. 2ND PLUG AT 420' WITH 80 SX CMT. 3RD PLUG AT 40' WITH 30 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4214			
4185	4195		

INVOICED
DATE 12-17-09
INV. NO. 2010060582

RECEIVED
KANSAS CORPORATION COMMISSION

OCT 27 2009

Remarks: USED 60/40 POZMIX 4% GEL BY QULAITY OIL WELL CEMENTING.

Plugged through: CSG

CONSERVATION DIVISION
WICHITA, KS

District: 01

Signed Stephen J Pfeifer
(TECHNICIAN)

RECEIVED
OCT 19 2009
KCC DODGE CITY

Form CR 275