

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-047-06938-00-00
Spot: SENW Sec/Twnshp/Rge: 23-25S-16W
1980 feet from N Section Line, 3300 feet from E Section Line
Lease Name: WILES Well #: 1
County: EDWARDS Total Vertical Depth: 4401 feet

Operator License No.: 5427
Op Name: D. R. LAUCK OIL CO., INC.
Address: 221 S BROADWAY STE 400
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	352		WITH 225 SX CMT 143.03
PLG		4401		
PROD	5.5	4434	2190	WITH 700 GAL CEALMENT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/22/2009 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 4130' & 5 SX CMT. PLUG AT 1050' WITH 15 SX GEL & 50 SX CMT. PLUG AT 390' WITH 60 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/22/2009 10:46 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED TO 4225' & 5 SX CMT WITH DUMP BAILER. 1ST PLUG AT 1080' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 390' WITH 60 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4337	4345		
4308	4312		

INVOICED
DATE 12-17-09
INV. NO. 2010060584

RECEIVED
NOV 02 2009
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: CSG

District: 01

Signed Richard W. Lacey
(TECHNICIAN)

RECEIVED
OCT 26 2009
KCC DODGE CITY