

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-23198-00-00
Spot: NESESE Sec/Twnshp/Rge: 14-16S-21W
990 feet from S Section Line, 330 feet from E Section Line
Lease Name: PUGH Well #: 2
County: NESS Total Vertical Depth: 4219 feet

Operator License No.: 5086
Op Name: PINTAIL PETROLEUM, LTD.
Address: 225 N.MARKET STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	305		WITH 185 SX CMT
PROD	5.5	4218	0	WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/12/2009 9:30 AM
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC
Proposal Rcvd. from: WAYNE WILSON Company: WHITETAIL CRUDE, INC Phone: (785) 798-3641

Proposed Plugging Method: PLUG AT 3950' WITH 100# HULLS & 25 SX CMT. PLUG AT 1500' WITH 50 SX CMT. WAIT ON CMT 2 HOURS. TEST CASING.

137.12

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/13/2009 5:00 PM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

PBTD @ 3960' WITH SAND & JUNK. 1ST PLUG RIHWT TO 3960' & PUMP 100# HULLS & 25 SX CMT. 2ND PLUG PULL TBG TO 1519'. PUMP 50 SX CMT. WAIT ON CMT 4 HOURS. TEST CASING TO 300 PSI. TOC @ 1500'. 3RD PLUG PERFORATE 5 1/2" @ 960'. PUMPED 170 SX CMT DOWN CASING. 4TH PLUG PUMPED 200 SX CMT DOWN 5 1/2" X 8 5/8" ANNULUS. 10/13/09: 5TH PLUG TOPPED OFF 4 1/2" WITH 50 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4112	4118		

INVOICED

DATE 12-17-09
INV. NO. 2010060589

RECEIVED

NOV 02 2009

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

KCC WICHITA

Plugged through: TBG

District: 01

RECEIVED

OCT 28 2009

KCC DODGE CITY

Signed

Jerry W. Stapleton
PINTAIL (TECHNICIAN)

Form CP 2/3