

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-12866-00-00
Spot: NWSENW Sec/Twnshp/Rge: 20-22S-11W
3630 feet from S Section Line, 3630 feet from E Section Line
Lease Name: AIKEN Well #: 2
County: STAFFORD Total Vertical Depth: 3640 feet

Operator License No.: 5920
Op Name: BANDY, TERRY P. DBA TE-PE OIL & G
Address: PO BOX 522
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	192		WITH 150 SX CMT
PLG		3616		
PROD	5.5	3640	1620	WITH 70 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/20/2009 2:45 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND BACK TO 3340' & 5 SX CMT. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 220' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

118.30

Plugging Proposal Received By: STEVE PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/20/2009 4:00 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SAND BOTTOM TO 3340' & 5 SX CMT WITH DUMP BAILER. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 220' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3600	3606		
3542	3550		
3448	3450		
3427	3429		
3390	3392		

INVOICED

DATE 12-17-09
INV. NO. 2010060591

RECEIVED

NOV 02 2009

KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OIL WELL CEMENTING.

Plugged through: CSG

District: 01

Signed

Richard M. Lacey

(TECHNICIAN)

RECEIVED

OCT 26 2009

KCC DODGE CITY

Form CP-2/3