

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-15561-00-00
Spot: SEWNNE Sec/Twnshp/Rge: 21-20S-12W
4290 feet from S Section Line, 1650 feet from E Section Line
Lease Name: GELWICKS Well #: 5
County: BARTON Total Vertical Depth: 3448 feet

Operator License No.: 3942
Op Name: MONROE, ORVILLE DBA BIG "O"
Address: 2820 PASEO DR
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	284	0	250 SX
PROD	5.5	3421	0	100 SX <u>112.06</u>

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/23/2009 10:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: ORVILLE MONROE Company: BIG "O" Phone: (620) 793-2134

Proposed Plugging Method: Ordered 425 sxs 60/40 pozmix - 4% gel - 500# hulls.
Well squeezed on backside from 1020' to surface.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/23/2009 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Ran tubing to 3100' - pumped 100 sxs cement with 300# hulls.
Pulled tubing to 2250' - pumped 100 sxs cement with 100# hulls.
Pulled to 1350' - pumped 120 sxs cement with 100# hulls - circulated cement to surface.
Pulled tubing - topped off with 15 sxs cement - stayed full.

Perfs:

Top	Bot	Thru	Comments
3421	3448		
3339	3343		
3305	3309		
3242	3244		
3214	3216		
3192	3197		
3164	3168		

RECEIVED
NOV 04 2009
KCC WICHITA

Remarks: QUALITY OIL WELL CEMENTING COMPANY

Plugged through: CSG

INVOICED
DATE 12-17-09
INV NO. 2010060593

District: 04

Signed Bruce Rodie
(TECHNICIAN) CM PR

OCT 30 2009

21-20-12W 53

CHARLES HULME DRLG #5 GELWICKS SE NW NE

Contr. CHAS HULME DRLG BARTON County


E 1853RB Comm. 7-31-57 Comp. 9-27-57 IP 99 BOPD/ARB
PHY POT

Tops	Depth	Datum
HEEB	3030	-1177
BR LM	3155	-1302
KC	3170	-1317
CONG	3400	-1517
ARB	3411	-1561
TD	3429	-1576

Casing
 8" 286
 5" 3416

 CO 3429: ACID 1000: 5 BOPH
 SWB 10 BOPH, NW

WORKMAN NW POOL



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS