

4-041989 15-163-00989-0001

10-13

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15- - 9-21-74

NE NE SW /4 SEC. 36, 10 S, 20 W  
2310 feet from S section line  
2970 feet from E section line

Operator license# 8168

Lease: Keller OWWO Well # 1

Operator: Helen A. Keller Davis

County: Rooks 121.23

Address: Keller & Son  
554 North County Line Rd  
Zurich, Kansas 67663-7050

Well total depth 3730 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface Pipe: 8 5/8 Inch 223 Feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:00 A.M. Day: 13 Month: October Year: 1998

Plugging proposal received from: Frank Taggart

Company: J. & F. Oil Company Phone: -

Were: 4 1/2" casing set at 3514' w/100 sxs cement. Perfs at 3392' - 3466'.  
Ordered 175 sxs 60/40 pozmix - 10% gel with 1/4# F.C. plus 400# hulls.  
Casing squeezed at 1415' w/450 sxs common cement (10-01-74). Re-squeezed at 1475' and  
2820' to 3050' with 175 sxs cement. Bottom plugged with sand from casing leak.

Plugging Proposal Received by: Dennis Hamel

Plugging operations attended by agent? All[ ], Part[ X ], None[ ]

Completed: Hour: 12:30 P.M., Day: 13, Month: October, Year: 1998

Actual plugging report: R.U. pulling unit to lay out tubing, rods and pump. Pulled rods and pump and laid out same - attempted to pull tubing which parted at 967'. R.I.H. with tubing to 900' to spot 55 sxs cement with 200# hulls and circulated to surface. P.O.O.H. with tubing and squeezed 4 1/2" casing with additional 75 sxs cement to Max. P.S.I. 600#. R.U. cementers to S.P. and squeezed 25 sxs cement with 100# hulls down 8 5/8" casing. Max. P.S.I. 300#.

Remarks:

Condition of casing(in hole): GOOD - BAD X Anhy.plug: YES X NO

Bottom plug(in place): YES X, CALC, NO Dakota plug: YES X, NO

Plugged through TUBING X CASING Elevation: G.L.

I did[ X ] / did not[ ] observe the plugging.

Dennis L. Hamel  
Rocks (agent)  
10-23-98  
Form CP-2/3

10-23-98  
60180