

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-147-30023-00-01
Spot: NWSWSE Sec/Twnshp/Rge: 31-1S-18W
990 feet from S Section Line, 2310 feet from E Section Line
Lease Name: HUFFSTUTTER D Well #: 4
County: PHILLIPS Total Vertical Depth: 3631 feet

Operator License No.: 31569
Op Name: BACH, JASON DBA BACH OIL PRODUC
Address: PO BOX 723
ALMA, NE 68920

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	205	0	w/135 sxs cmt
PROD	4.5	3630	0	w/150 sxs cmt

118.01

Well Type: EOR UIC Docket No: E08461.5 Date/Time to Plug: 10/27/2009 1:00 PM
Plug Co. License No.: 31569 Plug Co. Name: BACH, JASON DBA BACH OIL PRODUCTION
Proposal Rcvd. from: DALE FERLAND Company: BACH, JASON DBA BACH OIL PRO Phone: (758) 302-1435

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 4% gel - 600# hulls.
Tagged junk in the hole at 1155' - packer and tubing.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/27/2009 4:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 1140' - pumped 90 sxs 60/40 pozmix - 4% gel - circulated to surface.
Pulled all tubing. Hooked onto 4 1/2" casing - pumped 210 sxs 60/40 pozmix - 4% gel with 200# hulls.
Max. P.S.I. 750#. S.I.P. 700#.
Hooked to 8 5/8" x 4 1/2" annulus - pumped 75 sxs 60/40 pozmix - 4% gel.
S.I.P. 75#.

Perfs:

Top	Bot	Thru	Comments
3438	3550		

12-14-09
2010060534

RECEIVED
OCT 30 2009
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #37568.


Plugged through: TBG

District: 04

Signed Pat Bedore
(TECHNICIAN) CM

OCT 29 2009

6-162 Map No. _____
 OPER PETROLEUM MANAGEMENT, INC.
 Wichita, Kansas
 WELL #4 HUFFSTUTTER "D"
 CONTR Red Tiger Drlg.
 FIELD Huffstutter Field (LKc Oil)
 I.P. P 25 BOPD, NW, Miss 3438-3555 (OA)



STR 31-1S-18W
 SPOT NW SW SE
 CO PHILLIPS, Ks.
 ELEV 2232 KB

(KB Log)
 Top 3139 - 907
 Hb 3354 -1122
 Tor 3386 -1154
 Lan 3403 -1171
 BKc 3620 -1388
 RTD 3631 -1399
 LTD NA
 (KB Spl)
 Anh 1804
 B/Anh 1822
 RTD 3631

DST #1 (Lans) 3455-98, Op 60", R 15' SOCWCM & 3' FO,
 ISIP 237#/30", FP's 10-42#, FSIP 212#/30"
 DST #2 (Lans) 3535-65, Op 60", R 10' SOCM & 2' FO,
 ISIP 671#/30", FP's 11-32#, FSIP 263#/30", RTD 3631,
 Log, 4" @3630' w/150 Sx., CO 12/3552-55, 8/3494-96, 8/
 3480-82, 12/3455-58, 12/3438-41 (Lans), 1250A, § 1d, §
 1½ BOPH / tr AW/NT, POP, Co Pump 25 BOPD, NW, Lans
 3438-3555 OA, Gr NA - COMPLETED 6-22-65

Data Inc

MISC DATA
 GEOL Joe Rakaskas ELEV 2227 GR SPUD DATE 5-25-65
 FTG 2229 DF DRIG COMP
 SUPPT FR by DATA 5-25-65
 CSG 8" @205' w/135 Sx. - 4" @3630' w/150 Sx. COMP by 6-24-65