

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-147-20161-00-01
Spot: NWSENW Sec/Twnshp/Rge: 15-1S-18W
3690 feet from S Section Line, 3690 feet from E Section Line
Lease Name: O'NEILL A Well #: 4
County: PHILLIPS Total Vertical Depth: 3428 feet

Operator License No.: 31569
Op Name: BACH, JASON DBA BACH OIL PRODUC
Address: PO BOX 723
ALMA, NE 68920

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	215	0	w/unknown sxs cmt 111.41
PROD	4.5	3500	0	w/250 sxs cmt

Well Type: EOR UIC Docket No: E17599.3 Date/Time to Plug: 10/28/2009 12:30 PM
Plug Co. License No.: 31569 Plug Co. Name: BACH, JASON DBA BACH OIL PRODUCTION
Proposal Rcvd. from: DALE FERLAND Company: BACH, JASON DBA BACH OIL PRO Phone: (785) 302-1435

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 4% gel - 300# hulls - 7 sxs gel spacer.
Perforated at 1710' - 1120' - 260'.

Plugging Proposal Received By: PAT BEDORE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/28/2009 4:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3400' - pumped 7 sxs gel spacer - followed with 50 sxs 60/40 pozmix - 4% gel with 100# hulls.
Pulled tubing to 1730' - pumped 100 sxs 60/40 pozmix - 4% gel with 200# hulls.
Pulled tubing to 500' - pumped 40 sxs 60/40 pozmix - 4% gel to circulate to surface.
Pulled all tubing. Topped off 4 1/2" casing with 25 sxs 60/40 pozmix - 4% gel.
Hooked onto 8 5/8" x 4 1/2" annulus - pumped 35 sxs 60/40 pozmix - 4% gel.

Perfs:

Top	Bot	Thru	Comments
3343	3400		
12-14-09 2010060536			
RECEIVED OCT 30 2009 KCC WICHITA			

Remarks: ALLIED CEMENTING COMPANY-TICKET #37570.

Plugged through: TBG

District: 04

Signed

Pat Bedore

(TECHNICIAN)

CM

Handwritten initials

Form CP-2/3

OCT 29 2009

LELAND R. BAIRD

INFO RELEASED #4 O'NEILL "A"

15-1-18W C NW/4

1ST NATL BK BLDG LOGAN, KS. CONTR ABERCROMBIE DRILLING CTY PHILLIPS

GEOL STEVE POWELL FIELD LOGAN

E 2104 RB CM CARD ISSUED 5/10/73 IP P 25 80PD N/W LANS 3396-3400, 3378-88 3361-66, 3343-49

+	+
+	+
+	+

APR 15-147-20,161

LOG	TOPS	DEPTH	DATUM	
				8-5/8" 230, 5 1/2" 3540
ANH	1700	+ 404		DST (1) 3328-52/90-60, 15' SOCM + SFO, FBHP 537#, FP 23-30#
TOP	3066	- 962		
HEEB	3264	-1160		DST (2) 3352-72/60-60, 15' OIL SP M, FBHP 601#, FP 20-20#
TUR	3292	-1188		
LANS	3310	-1206		DST (3) 3372-90/90-60, 3' CO, 10' OCM, FBHP 131#, FP 15-23#
BKC	3530	-1426		
TD	3543	-1439		DST (4) 3392-3412/60-60, 10' M W/RBSO, FBHP 490#, FP 15-15#
				PF 1/3399, 1/3398, A 500, REC LD, SWB 6BOPH/3HRS, OFF BTM, RE-AC 1500, REC LD, SWB 10 1/2 BOPH, PF 1/3380, 1/3382, 1/3384, BP 3392, A 500, PULL PLUG, NO INCREASE IN OIL, PF 1/3344, 1/3345, BP 3352, A 500 GAL, SWB LD, SWB 5BOPH, PF 3396-3400, 3378-88, 3361-3366, 3343-49, POP
				INFO RELEASED: 7/18/74

INDEPENDENT OIL & GAS SERVICE WICHITA, KANSAS