

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-00241-00-00
Spot: E2 Sec/Twnshp/Rge: 19-32S-40W
2448 feet from S Section Line, 1389 feet from E Section Line
Lease Name: FORTENBAUGH Well #: 1
County: MORTON Total Vertical Depth: 2380 feet

Operator License No.: 5952
Op Name: BP AMERICA PRODUCTION COMPANY
Address: 2225 W OKLAHOMA AVE
ULYSSES, KS 67880

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	9.625	542		WITH 550 SX CMT
PROD	7	2365		WITH 600 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/06/2009 9:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: KEVIN STRUBE Company: BP AMERICA Phone: (620) 356-1237

Proposed Plugging Method: FREE POINT TBG-CMT OFF. CIRCULATE CMT TO SURFACE. CHECK & TOP OFF BACKSIDE.

77.35

Plugging Proposal Received By: STEVE PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/06/2009 2:30 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

ROD FISH LEFT IN HOLE @ 1200'. TBG FISH LEFT IN HOLE @ 950'. 1ST PLUG FREE POINT TBG @ 1000'. CUT @ 950'. RIHWT TO 950'. PUMP 75 SX CMT & 100# HULLS. 2ND PLUG POOH. TAG CMT @ 450'. RIHWT TO 450'. CIRCULATE CMT TO SURFACE WITH 85 SX CMT. 3RD PLUG PUMP 1 SX CMT DOWN 8 5/8" X 5 1/2" ANNULUS. SHUT IN PRESSURE 300#.

Perfs:

12-14-09
2010060541

Remarks: USED CLASS C CMT W/2% BENTONITE BY ORR ENTERPRISES.

Plugged through: TBG

RECEIVED
KANSAS CORPORATION COMMISSION

OCT 27 2009

CONSERVATION DIVISION
WICHITA, KS

District: 01

Signed

Jack MacLaskey
(TECHNICIAN)

RECEIVED
OCT 12 2009
KCC DODGE CITY

Form CP 2/09