

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-093-20334-00-00
Spot: SWNE Sec/Twnshp/Rge: 13-21S-35W
1980 feet from N Section Line, 1980 feet from E Section Line
Lease Name: UNRUH Well #: 1
County: KEARNY Total Vertical Depth: 2750 feet

Operator License No.: 32198
Op Name: PETROSANTANDER (USA) INC.
Address: 6363 WOODWAY DR STE350
HOUSTON, TX 77057

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1100		
CIBP		2358		WITH 2 SX CMT 89.38
SURF	8.625	541		WITH 300 SX CMT
PROD	4.5	2738	0	WITH 200 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/05/2009 12:30 PM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Rcvd. from: PETE KUNEYL Company: PETROSANTANDER Phone: (620) 275-2388

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/05/2009 5:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

TOP OF 2 3/8" TBG FISH @ 2365'. CIBP @ 2358' WITH 2 SX CMT. CIBP @ 1100'. TEST CASING TO 800# & HELD. PERFORATE @ 1075'. PUMP 75 SX CMT, 50# HULLS & 9 BALL SEALERS THEN 70 SX CMT. PRESSURE TO 400# & HELD. PUMP 105 SX CMT DOWN ANNULUS. PRESSURED TO 300# & HELD.

Perfs:

Top	Bot	Thru	Comments
2644	2658		KRIDER

12-14-09
2010060566

RECEIVED
KANSAS CORPORATION COMMISSION

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC CEMENTING.

OCT 27 2009

Plugged through: CSG

CONSERVATION DIVISION
WICHITA, KS

District: 01

RECEIVED

OCT 12 2009

KCC DODGE CITY

Signed

Ken Jehlik

(TECHNICIAN)