

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-02721-00-00
Spot: NWNWSE Sec/Twnshp/Rge: 35-20S-9W
2282 feet from S Section Line, 2221 feet from E Section Line
Lease Name: TOBIAS SIMPSON UT Well #: 6-10
County: RICE Total Vertical Depth: 3387 feet

Operator License No.: 5363
Op Name: BEREXCO, INC.
Address: PO BOX 20380
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP	5.5	3262		
SURF	8.625	205		175 SX
PROD	5.5	3384		100 SX

110.08

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/09/2009 4:15 PM
Plug Co. License No.: 31720 Plug Co. Name: STEWART WELL SERVICE INC
Proposal Rcvd. from: ROBERT GRANT Company: BEREXCO INC Phone: (316) 772-8160

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL
Date/Time Plugging Completed: 09/09/2009 6:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. PERFORATE AT 1175', 750', AND 255'. RUN TUBING TO 3158' AND PUMP 4 SX'S SAND FOLLOWED BY 15 SX'S CEMENT. PULL TUBING TO 3050' AND PUMP 5 SX'S GEL. PULL TUBING TO 1198' AND PUMP 35 SX'S CEMENT. PULL TUBING TO 753' AND PUMP 35 SX'S CEMENT. PULL TUBING TO 280' AND CIRCULATE TO SURFACE. PULL TUBING OUT AND TOP OFF. CONNECTED ONTO BACKSIDE AND PUMPED 30 SX'S CEMENT.

Perfs:

Top	Bot	Thru	Comments
3331	3339		
3326	3332		
3262			

12-14-09
2010060538
RECEIVED
OCT 26 2009
KCC WICHITA

Remarks: 60-40 POZ, 4% GEL. PERF TECH #6616. ALLIED TICKET #20124.

Plugged through: TBG

District: 02

Signed Virgil Clothier
(TECHNICIAN)