

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-047-20823-00-00
Spot: NWSWNW Sec/Twnshp/Rge: 23-26S-16W
3672 feet from S Section Line, 4976 feet from E Section Line
Lease Name: ELLEGE Well #: 4
County: EDWARDS Total Vertical Depth: 4490 feet

Operator License No.: 5364
Op Name: BEREN CORPORATION
Address: PO BOX 20380
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	452		WITH 350 SX CMT
PLG	5.5	4440		
PROD	5.5	4489	2030	WITH 250 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/09/2009 8:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 935-2537

Proposed Plugging Method: SAND TO 4340' & 5 SX CMT. PLUG AT 1075' WITH 15 SX GEL & 50 SX CMT. PLUG AT 480' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.
145.93

Plugging Proposal Received By: RICHARD LACEY Witness Type: PARTIAL
Date/Time Plugging Completed: 10/09/2009 12:35 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED TO 4300' & 5 SX CMT WITH DUMP BAILER. 1ST PLUG AT 1070' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 480' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4390	4393		4 SPF

12-14-09
2010060539

RECEIVED
KANSAS CORPORATION COMMISSION

OCT 27 2009

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

Signed Richard M. Lacey
(TECHNICIAN)

RECEIVED

OCT 15 2009

KCC DODGE CITY