

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-207-27510-00-00
Spot: NWSWNWSE Sec/Twnshp/Rge: 29-23S-15E
1950 feet from S Section Line, 2570 feet from E Section Line
Lease Name: BOWERS Well #: N-3
County: WOODSON Total Vertical Depth: 1361 feet

Operator License No.: 31280
Op Name: BIRK, BRIAN L. DBA BIRK PETROLEU
Address: 874 12TH RD SW
BURLINGTON, KS 66839

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8	40	0	

44.23

Well Type: OK DH KCCPT UIC Docket No: _____ Date/Time to Plug: 10/20/2009 1:00 PM

Plug Co. License No.: 31280 Plug Co. Name: BIRK, BRIAN L. DBA BIRK PETROLEUM

Proposal Rcvd. from: BRIAN BIRK Company: BIRK, BRIAN L. DBA BIRK PETRO Phone: (620) 364-5875

Proposed Plugging Method: THIS WELL CONSISTED OF AN UNCASD BORE TO 1361'. THE PLUGGING PROPOSAL WAS TO PLACE A 40' CEMENT PLUG AT T.D., A 50' CEMENT PLUG AT 700', AND A CONTINUOUS CEMENT PLUG FROM 250' TO SURFACE.

Plugging Proposal Received By: CLAYTON TITEL
Date/Time Plugging Completed: 10/20/2009 5:00 PM

WitnessType: NONE
KCC Agent: CLAYTON TITEL

Actual Plugging Report:

PIPE WAS RAN INTO THE WELL TO T.D.. 10 SACKS OF CEMENT WERE PUMPED THROUGH THE PIPE TO T.D.. THE PIPE WAS PULLED TO 700' AND 10 SACKS OF CEMENT WERE PUMPED TO THAT DEPTH. THE PIPE WAS PULLED TO 250'. CEMENT WAS PUMPED INTO THE PIPE UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING AT SURFACE. THE PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

Perfs:

RECEIVED
KCC DISTRICT #3

OCT 21 2009 CPT

CHANUTE, KS

RECEIVED
KANSAS CORPORATION COMMISSION

OCT 26 2009

CONSERVATION DIVISION
WICHITA, KS

Remarks:

Plugged through: TBG

12-14-09
2010060540

District: 03

Signed

Clayton P. Titel

(TECHNICIAN)