

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-115-19155-00-00  
Spot: N2NWSWSW Sec/Twnshp/Rge: 16-21S-5E  
1099 feet from S Section Line, 4976 feet from E Section Line  
Lease Name: STRAIT RANCH Well #: 10  
County: MARION Total Vertical Depth: 2300 feet

Operator License No.: 6655  
Op Name: CRAWFORD, GARRY F. DBA CRAWFO  
Address: PO BOX 727  
EL DORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	0		
PROD 7		0		74.75

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: \_\_\_\_\_  
Plug Co. License No.: 5870 Plug Co. Name: PHILLIPS WELL SERVICE, INC.

Proposal Rcvd. from: \_\_\_\_\_ Company: \_\_\_\_\_ Phone: \_\_\_\_\_

Proposed Plugging Method: TAG BOTTOM, SAND TO 2200 CAP W/10 SXS. PULL UP PERF @ 250' MINIMUM & CIRCULATE CEMENT UP & AROUND BACK SIDE TO SURFACE. PULL TUBING \$ TOP OFF

Plugging Proposal Received By: \_\_\_\_\_ Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 09/24/2009 4:10 PM KCC Agent: SHANE JONES

Actual Plugging Report: \_\_\_\_\_ Perfs: \_\_\_\_\_

PHILLIPS WELL SERVICE RAN 2" IN & TAGGED @ 2300'. THEY PULLED UP TO 2200 DUMPED SAND. CONSOLIDATED ONLY HAS ENOUGH SAND TO FILL 50' OF 7". SO CAPPED SAND W/20 SX 60/40 POS W/4% GEL. DUG OUT SURFACE AND CUT WINDOW IN SIDE OF SURFACE CASING. PHILLPS WELL SERVICE PULLED TUBING. DYNA-LOG RAN DOWN AND TAGGED BOTTOM PLUG @ 2184'. DYNA LOG PULLED UP & PERFED 4 SHOTS 251'-250'. PHILLIPS WELL SERIVCE RAN 8 JOINTS INTO 248'. CONSOLIDATED PUMPING WATER TO CHECK CIRCULATION. GOOD CIRCULATION. CONSOLDIATED CIRCULATED CEMENT UP THE BACKSIDE & TO SURFACE OF 7". PHILLPS WELL SERVICE PULLED TUBING & CONSOLIDATED TOPPED OF WELL. FINISHED AT 4:10 PM. 240 SXS 60/40 POS W/4% GEL TK #23048

12-14-09  
2010060543

RECEIVED  
OCT 28 2009  
KCC WICHITA

Remarks:

Plugged through: TBG

District: 02

Signed [Signature]  
(TECHNICIAN)