

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-23498-00-00
Spot: E2SW Sec/Twnshp/Rge: 27-22S-11W
1330 feet from S Section Line, 2130 feet from W Section Line
Lease Name: CURTIS Well #: 2
County: STAFFORD Total Vertical Depth: 3648 feet

Operator License No.: 33936
Op Name: GRIFFIN, CHARLES N.
Address: 177 OLD HWY 40 PO BOX 670
BYERS, CO 80103

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	3410		
SURF	8.625	250		
PROD	5.5	3646	2650	WITH 150 SX CMT

118.56

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/05/2009 11:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND BOTTOM TO 3240' & 5 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 280' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/05/2009 12:36 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED BOTTOM TO 3220' & 5 SX CMT WITH DUMP BAILER. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 280' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3424	3426		KC- J
3383	3388		KC- H
3318	3323		KC- F
3290	3292		KC- D

12-14-09
2010060551

RECEIVED
KANSAS CORPORATION COMMISSION

OCT 19 2009

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY QULAITO OILWELL CEMENTING.

Plugged through: CSG

District: 01

Signed

Richard W. Lacey

(TECHNICIAN)

RECEIVED

OCT - 9 2009

KCC DODGE CITY

Form CP-2/3