

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-02623-00-00  
Spot: NESWSE Sec/Twnshp/Rge: 10-14S-14W  
990 feet from S Section Line, 1650 feet from E Section Line  
Lease Name: SAM BOXBERGER Well #: 7  
County: RUSSELL Total Vertical Depth: 3097 feet

Operator License No.: 30317  
Op Name: J.H. R., INC.  
Address: 533 WASHINGTON RD STE 100  
BRIDGEVILLE, PA 15017

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	10.75	160	0	w/unknown sxs cmt
PROD 7		2992	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/28/2009 8:30 AM  
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING  
Proposal Rcvd. from: WARD CRAIG Company: J.H.R., INC. Phone: (785) 483-1543

Proposed Plugging Method: Ordered 390 sxs 60/40 pozmix - 4% gel - 400# hulls - 13 sxs gel.  
Perf at 810' - 1600'.  
100.65

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/28/2009 12:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:  
Ran tubing 2800' - pumped 13 sxs gel - followed with 100 sxs cement with 300# hulls mixed in.  
Pulled tubing to 1600' - pumped 75 sxs cement with 100# hulls.  
Pulled tubing to 800' - pumped 145 sxs cement - cement circulated.  
POOH. Hooked on Braden head. Max. P.S.I. 200#. Held.  
Filled casing up - pumped 20 sxs cement.

Perfs:  
12-14-09  
2010060554

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #3954.  
Plugged through: TBG

RECEIVED  
OCT 30 2009  
KCC WICHITA

District: 04 Signed Ray A Dinkel (TECHNICIAN) CM

OCT 29 2009

15-167-62623-0000

H.H. BLAIR & W.L. HARTMAN #7 S BOXBERGER #33      Arb 10-14-14w  
 NE S.W. SE

Contr. \_\_\_\_\_ RUSSELL \_\_\_\_\_ County

E. 1842 Comm. 12-27-48 Comp. 2-25-49 IP 150 BOPD & 65 BW

Tops	Depth	Datum
ANH	793	+1049
TOP	2630	-788
BK LM	2933	-1091
LANS	2991	-1149
T.D.	3097	-1255

Casing  
 10" 160 ACID 5000  
 7" 2992 PMP 10 BOPD & 10 BWFH/5 HPS  
 EST 150 BOPD & 65 BW

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS