

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-147-00163-00-00  
Spot: SESENE Sec/Twnshp/Rge: 34-4S-20W  
2970 feet from S Section Line, 330 feet from E Section Line  
Lease Name: SHAW Well #: 1  
County: PHILLIPS Total Vertical Depth: 3394 feet

Operator License No.: 9559  
Op Name: PATTERSON, JERRY DBA JERRY PATT  
Address: PO BOX 307  
LOGAN, KS 67646

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	213	0	w/225 sxs cmt
PROD	4.5	3393	0	w/180 sxs cmt

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/20/2009 8:30 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: JERRY PATTERSON Company: JERRY PATTERSON OIL Phone: (785) 689-4897

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 300# hulls.  
Packer stuck in the hole at 1755'.  
Perfed at 1500' and 1150'.  
110.31

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/20/2009 10:30 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 1550' - pumped 150 sxs 60/40 pozmix - 4% gel with 200# hulls.  
Pulled tubing to 1000' - pumped 50 sxs 60/40 pozmix - 4% gel with 100# hulls to circulate to surface.  
Pulled all tubing. Hooked onto 4 1/2" casing - pumped 35 sxs 60/40 pozmix - 4% gel.  
Max. P.S.I. 400#.  
Hooked onto 8 5/8" surface pipe - pumped 10 sxs 60/40 pozmix - 4% gel down 8 5/8" x 4 1/2" annulus.  
S.I.P. 200#.

Perfs:

Top	Bot	Thru	Comments
3238	3248		
3224	3230		

RECEIVED  
OCT 26 2009  
KCC WICHITA

Remarks: SWIFT CEMENTING SERVICES-TICKET #16753.

Plugged through: TBG

District: 04

Signed Pat Bedore  
(TECHNICIAN)

CM *[Signature]*

12-14-09  
2010060555

OCT 21 2009

