

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-01820-00-00
Spot: SWNWNE Sec/Twnshp/Rge: 17-12S-15W
4290 feet from S Section Line, 2310 feet from E Section Line
Lease Name: AMERICAN INVESTMENT COMPANY Well #: 1
County: RUSSELL Total Vertical Depth: 2992 feet

Operator License No.: 7628
Op Name: LORENZEN OIL COMPANY, INC.
Address: PO BOX 67
ARLEY, AL 35541

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	10.75	895	0	w/unknown sxs cmt
PROD	7	2989	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/16/2009 9:00 AM
Plug Co. License No.: 32128 Plug Co. Name: ROME CORPORATION DBA WESTERN WELL SERVICE
Proposal Rcvd. from: AVEN WEAVERLING Company: PRODUCTION DRILLING Phone: (785) 623-3221

Proposed Plugging Method: 10-16-2009 - Ordered 150 sxs 60/40 pozmix - 4% gel - 600# hulls - 25 sxs gel.
10-19-2009 - Ordered 300 sxs 60/40 pozmix - 4% gel.
Perf at 1550' - 890' - 425' - 150'. 97.24

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/19/2009 3:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

10-16-2009 - Ran tubing to 2875' - pumped 25 sxs gel - followed with 50 sxs cement with 250# hulls mixed in.
Pulled tubing to 1550' - pumped 100 sxs cement with 350# hulls mixed in.
POOH and shut down.
10-19-2009 - Ran tubing to 890' - pumped 145 sxs cement - circulated.
POOH and hooked up to casing - pumped 40 sxs cement. Max. P.S.I. 200#.
Dugged down 20' to 25' - no surface pipe in well - had cement/water at surface.
Hooked up to casing. Max. P.S.I. 500#. Pumped 45 sxs in cellar.

Perfs:

12-14-09
2010060559

RECEIVED
OCT 26 2009
KCC WICHITA

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #3839 AND #3917.

Plugged through: TBG

District: 04

Signed

Ray A. Dinkel

(TECHNICIAN)

CM

PKH