

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-25354-00-00
Spot: NWSWN Sec/Twnshp/Rge: 31-17S-14W
1590 feet from N Section Line, 230 feet from W Section Line
Lease Name: MATER UNIT Well #: 1
County: BARTON Total Vertical Depth: 3570 feet

Operator License No.: 5259
Op Name: MAI OIL OPERATIONS, INC.
Address: 8411 PRESTON RD STE 800
DALLAS, TX 75225

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	980		

116.03

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 10/20/2009 12:00 AM
Plug Co. License No.: 33350 Plug Co. Name: SOUTHWIND DRILLING, INC.
Proposal Rcvd. from: JAY Company: MAI OIL OPEERATIONS, INC. Phone: (214) 219-8883

Proposed Plugging Method: Ordered 185 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: BRUCE RODIE WitnessType: NONE
Date/Time Plugging Completed: 10/20/2009 4:45 AM KCC Agent: BRUCE RODIE

Actual Plugging Report:

1st. Plug at 3525' w/25 sxs.
2nd. Plug at 1030' w/40 sxs.
3rd. Plug at 420' w/80 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.

Perfs:

RECEIVED
OCT 26 2009
KCC WICHITA

12-14-09
20100 60560

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed

Bruce Rodie

(TECHNICIAN)

CM

OCT 20 2009