

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-113-21013-00-00  
Spot: SWSWNE Sec/Twnshp/Rge: 30-20S-5W  
2977 feet from S Section Line, 2398 feet from E Section Line  
Lease Name: ANTON MATTSON Well #: 5  
County: MCPHERSON Total Vertical Depth: 3410 feet

Operator License No.: 31528  
Op Name: KELSO, MIKE OIL, INC.  
Address: PO BOX 467  
CHASE, KS 67524

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	212		140 SX
PROD	5.5	3409	2426	175 SX

110.83

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/21/2009 11:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKES TESTING & SALVAGE Phone: (620) 938-2537

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: B. J. HOPE Witness Type: PARTIAL  
Date/Time Plugging Completed: 10/21/2009 2:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SAND PERFS TO 3260' AND CAP WITH 5 SK'S CEMENT. CUT CASING AT 2426' AND PULL TO 825' AND PUMP 35 SX'S CEMENT. PULL CASING TO 400'. LET CEMENT SET FOR 1 HR. AND RETAGGED AT 600'. PUMP 35 SX'S CEMENT AT 400'. PULL CASING TO 250' AND CIRCULATE CEMENT TO SURFACE. PULL CASING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3314	3356		CSG

12-14-09  
2010060562

RECEIVED  
OCT 26 2009

KCC WICHITA

Remarks: 60-40 POZ, 4% GEL. COPELAND TICKET #C-35688

Plugged through: CSG

District: 02

Signed

*Virgil Clothier*

(TECHNICIAN)

*AG*