

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-22239-00-00  
Spot: W2W2SW Sec/Twnshp/Rge: 16-20S-10W  
1320 feet from S Section Line, 4720 feet from E Section Line  
Lease Name: SPECHT B Well #: 6  
County: RICE Total Vertical Depth: 3370 feet

Operator License No.: 32846  
Op Name: PREMIER OIL & EXPLORATION INC  
Address: 1100 AIRPORT RD  
HUTCHINSON, KS 67501

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	3210		
CIBP	5.5	3300		
SURF	8.625	217		
PROD	5.5	3369		

109.53

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/13/2009 9:00 AM  
Plug Co. License No.: 32098 Plug Co. Name: CLASSIC WELL SERVICE, INC.  
Proposal Rcvd. from: ALAN Company: CLASSIC WELL SERVICE Phone: \_\_\_\_\_

Proposed SEE BELOW  
Plugging  
Method:

Plugging Proposal Received By: GREG EVES Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 10/13/2009 2:30 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, RUN SCRAPER TO 3200'. PULL SCRAPER AND PERFORATE AT 1300', 900, AND 270' RUN TUBING TO 3166' AND PUMP 35 SX'S CEMENT WITH COTTON HULLS. PULL TUBING TO 1300' AND PUMP 35 SX'S CEMENT. PULL TUBING TO 900'. LET SET FOR 1 HR. TRIED TO TAG CEMENT - COULD NOT TAG. RUN TUBING BACK DOWN TO 1300' AND PUMP 35 MORE SX'S CEMENT WITH 100#S COTTON HULLS. PULL TUBING TO 800'. LET SET FOR 1 HR AND TAGGED CEMENT AT 1575'. RUN TUBING BACK DOWN TO 1300' AND PUMP 50 SX'S CEMENT, GETTING PARTIAL CEMENT RETURNS. PULL TUBING TO 900' AND PUMP 35 SX'S CEMENT. PULL TUBING TO 270' AND CIRCULATE CEMENT TO SURFACE. CIRCULATED CEMENT ON BACKSIDE OF 5.5" ALSO. PULL TUBING OUT OF HOLE AND TOP OFF. USED 315 SX'S TOTAL.

Perfs:

Top	Bot	Thru	Comments
3271	3278	CSG	
3250	3256	CSG	
3160	3162	CSG	
3146	3150	CSG	
3126	3130	CSG	

12-16-09  
2010060569

RECEIVED  
OCT 26 2009

Remarks: 60-40 POZ, 4% GEL. COPELAND CEMENT #C-32949. LOG TECH OF KS.

KCC WICHITA

Plugged through: TBG

District: 02

Signed Virgil Clothier  
(TECHNICIAN)

PKG