

15-065-01757-0000

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 30 1971  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name ~~R. W. Watchous,~~ Palomino Petroleum AUB KCC

Complete Address 304 Insurance Building, Wichita, Kansas.

Lease Name Lewis Well No. 3

Location NE-SW-NW Sec. 23 Twp. 10 Rge. (E) (W) 21

County Graham Total Depth 3732'

Abandoned Oil Well X Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Russ Casing Pulling, Incorporated,

Address Box #1082, Great Bend, Kansas. License No. 623

Operation Completed: Hour 1:00 PM Day 24 Month 12 Year 1971

The above well was plugged as follows:

226'--8 5/8" Surface casing, cement circulated.

3728'--5 1/2" Casing cemented on bottom with 100 Sx. DV tool set @ 1618' with cement circulated to surface with 485 Sx.

Squeezed 5 1/2" casing initially with 2 sacks hulls and 30 Cu. Ft. cement then 27 sacks gel from 3700' to 1000' and finally 125 Cu. Ft. cement from 1000' to bottom of cellar.

Maximum pump-in pressure-300#. Final shut-in pressure-100#.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Dechula  
Well Plugging Supervisor

DATE 1-7-72

INV. NO. 4872-W