

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 149-42

LOCATION NE NE NE

SEC. 23 TWP. 10 RGE. 21

Dry Hole _____ Abandoned Oil Well x Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 3 Lease Pierce

Operator Derby Oil Co Address Wichita, Kans

Field _____ County Graham

Total Depth 3761 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 250' circulated with cement - 4 1/2" at 3745' with 100 sax cement behind.

Filled with chat to 3730', set 4 sax cement with dump bailer, pulled 3100' 4 1/2", filled hole with mud to 250', set rock bridge and 15 sax cement, mud to 40', set rock and 10 sax cement to bottom cellar.

PLUGGING
FILE SEC 23 T 10 R 21
BOOK PAGE 149 LINE 4v

APR 18 1952

CONSERVATION DIVISION
WICHITA, KANSAS

04-18-52

District Conservation Agent

Date 4-16-52