

15-065-01761-0000

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 122-25

LOCATION NW SW NE

SEC. 23 TWP. 10 RGE. 21W

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 1 Lease Pierce

Operator Anderson-Prichard Address Box 142 Great Bend, Kans

Field \_\_\_\_\_ County Graham

Total Depth 3700 Feet.

Plugging Contractor Forbes Casing Pulling Co

Plugging Contractor's License No. 49

Address \_\_\_\_\_

(Describe briefly the manner in which the well was plugged)

8 5/8" at 277' circulated with cement - 5 1/2" at 3755' with  
125 sax cement behind.

Filled with rock to 3740', set 4 sax cement with dump bailer,  
pulled 3033' 3 1/2" - pumped hole full mud (20) sax Aquagel -  
pumped cementing plug to 250' followed by 80 sax cement,  
filling hole with cement 250' to 0'.

Mudding and cementing by Halliburton Co.

**PLUGGING**  
FILE SEC 23 T 10 R 21W  
BOOK PAGE 122 LINE 25

**RECEIVED**  
STATE CORPORATION COMMISSION  
SEP - 8 1953  
CONSERVATION DIVISION  
Wichita, Kansas

Edmond Kelly  
District Conservation Agent  
Date 9-5-53