

15-065-00111-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
DEC 30 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name E. W. Watchous, Palomino Petroleum ^{ANB} _{KCC}
Complete Address 304 Insurance Building, Wichita, Kansas.
Lease Name Lewis Well No. 1
Location NE-NE-NW Sec. 23 Twp. 10 Rge. (E) (W) 21
County Graham Total Depth 3784'
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Russ Casing Pulling, Incorporated,
Address Box #1082, Great Bend, Kansas. License No. 623
Operation Completed: Hour 9:30 AM Day 24 Month 12 Year 1971

The above well was plugged as follows:

272'--8 5/8" Surface casing, cement circulated.
3781'--5 1/2" Production casing cemented on bottom with 100 Sx. 5 1/2" casing has been
squeezed thru hole @ 1149' with 140 Sx. cement to 2200#. No recovery of casing.
Squeezed 5 1/2" casing initially with 2 sacks hulls and 30 Sx. cement from 3784' to
3700' then 27 sacks gel from 3700' to 1000' and finally 125 Sx. cement from 1000'
to bottom of cellar. Maximum pump-in pressure-200#. Final shut-in pressure-50#
(mudding and cementing operations by Allied Cementing Inc.).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Pichalo
Well Plugging Supervisor

DATE 1-7-72

INV. NO. 4890-W