

KANSAS



STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 26 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Bankoff & Leben,

Complete Address: 815 Wichita Plaza Building, Wichita, Kansas.

Lease Name Rudman Well No. 1

Location NE-NE-SE, Sec. 5 Twp. 10 Rge. (E) (W) 21

County Graham Total Depth 3524

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Leben Drilling, Incorporated,

Address: Box #486, Great Bend, Kansas. License No.

Operation Completed: Hour 9:45 AM Day 23 Month 8 Year 1968

The Above well was plugged as follows:

209'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 690'.

Circulated hole with heavy mud. Pulled DP to 900' and displaced 100 Sx. cement thru
DP from 900' to 580'. Pulled DP to 215' and displaced 20 Sx. cement thru DP from
215' to 155'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: N. L. Nichol
Well Plugging Supervisor

INVOICED
DATE 8/26/68
INV. NO. 8351-41