

*21*

KANSAS

Form CP-3  
Rev. 6-26-62

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
4-4-1969  
APR 4 1969  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Phillips Petroleum Company,

Complete Address: Box #287, Great Bend, Kansas.

Lease Name Noah Well No. 1

Location NW-NW-NW Sec. 2 Twp. 10 Rge. (E) (W) 21

County Graham Total Depth 3870'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Knight Casing Pulling Company, Incorporated,

Address: Box #105, Chase, Kansas. License No. 624

Operation Completed: Hour 2:30PM Day 2 Month 4 Year 1969

The Above well was plugged as follows:

1789'--8 5/8" Surface casing, cement circulated with 1050 Sx.  
3820'--5 1/2" Production casing cemented on bottom with 200 Sx. Well plugged back to  
3770'. Top of perforations @ 3494'. Fluid level in 85/8" casing @ 948 before squeezing.

Pushed plug to 3450', sanded back to 3400' and set 5 Sx. cement with dump bailer.

Pulled 5 1/2" casing and squeezed with initially 35 sacks gel from 1600' to 200' then  
60 Sx. cement from 200' to bottom of cellar. Maximum pump-in pressure--500#. Final  
shut-in pressure--300#. (Recovered 2504'--5 1/2" casing).

(Mudding and cementing operations performed by Allied Cementing Co., Inc.)

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 4/4/69  
INV. NO. 9548-U

Signed: *W. L. J. J. J.*  
Well Plugging Supervisor