

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
12-11-1967
DEC 11 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name John O. Farmer, Incorporated.

Complete Address Box #352, Russell, Kansas.

Lease Name Sutor Well No. A-2

Location NE-SW-NE Sec. 2 Twp. 10 Rge. (E) (W) 21

County Graham Total Depth 3854'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Allied Cementing Company, Incorporated.

Address Box #207, Russell, Kansas. License No. _____

Operation Completed: Hour 2:00 PM Day 6 Month 12 Year 1967

The above well was plugged as follows:

165'--8 5/8" Surface pipe, cement circulated with 100 Sx.
3840'--5 1/2" casing cemented on bottom with 100 Sx. 5 1/2" squeezed @ 1044' with 150 Sx.
cement, cement circulated. String of tubing left in hole.

Squeezed hole initially with 19 sacks gel and followed with 35 Sx. cement from 1350'
to 900' then 5 sacks gel from 900' to 200' and followed with 10 Sx. cement from 200'
to 120' then 1 sack gel from 120' to 40' and followed with 5 Sx. cement from 40' to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Nichols
Well Plugging Supervisor

INVOICED
DATE 12/12/67
INV. NO. 6885-W