



DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION SW SW NE

SEC. 2 TWP. 10 RGE. 21

Lost Hole

Dry Hole _____ Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. A-1 Lease _____ Sutor _____

Operator Jones Shelburne Farmer Address Russell, Kans

Field _____ County Graham

Total Depth 3845 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 165' circulated with cement - 5 1/8" at 3845'
Lost bailer in hole, tried to drill it up,
Set rock and 5 sax cement with dump bailer to 3800',
pulled 1650', 5 1/8", pumped hole full rotary mud to 160',
set rock bridge and 20 sax cement, filled with mud to 30'
set wood plug and 10 sax cement to bottom cellar.

RECEIVED
STATE CORPORATION COMMISSION

NOV - 2 1950
11-2-1950
CONSERVATION DIVISION
Wichita, Kansas

John J. [Signature]
District Conservation Agent

Date 10-31-50

PLUGGING
FILE SEC 2-T-10-R-21W
BOOK PAGE 39 LINE 44