

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
2-12-1973
FEB 12 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Phillips Petroleum Company,

Complete Address Box #287, Great Bend, Kansas.

Lease Name Noah Well No. 5

Location NW-SW-NW Sec. 2 Twp. 10 Rge. (E) (W) 21

County Graham Total Depth 3840'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling Company, Incorporated,

Address Box #405, Chase, Kansas. License No. 624

Operation Completed: Hour 12:00 M Day 2 Month 2 Year 1973

The above well was plugged as follows:

1809'--8 5/8" Surface casing, cement circulated with 1000 Sx.

3823'--5 1/2" Production casing cemented on bottom with 200 Sx. Top of perforations @ 3510'.

Sanded well back to 3500' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing (2700'), found top of fluid @ 1051'. Built wood and rock bridge from 1051' to 1000' and filled hole from 1000' to bottom of cellar with 13 Yards Redi-Mix cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. J. Nichols
Well Plugging Supervisor

DATE 2/12/73
INV. NO. 6957-W