

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
12-11-1967
DEC 11 1967

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name John O. Farmer, Incorporated,

Complete Address Box #352, Russell, Kansas.

Lease Name McClellan Well No. 8

Location SE-SW-SE Sec. 2 Twp. 10 Rge. (E) (W) 21

County Graham Total Depth 3835'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Allied Cementing Company, Incorporated,

Address Box #207, Russell, Kansas. License No.

Operation Completed: Hour 12:15 PM Day 6 Month 12 Year 1967

The above well was plugged as follows:

165'--8 5/8" Surface pipe, cement circulated with 100 Sx.

3821'--5 1/2" casing cemented on bottom with 75 Sx. 5 1/2" squeezed @ 1430' with 200 Sx, cement circulated. String of tools left in hole.

Squeezed 5 1/2" with initially 19 Sx. gel ~~from~~ and followed with 35 Sx. cement from 1350'

to 900' then 5 sacks gel from 900' to 200' and followed with 10 Sx. cement from 200'

to 120' then 1 sack gel from 120' to 40' and followed with 5 Sx. cement from 40' to

bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichols
Well Plugging Supervisor

DATE 12/12/67
INV. NO. 6884-W