



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
3-23-1973  
MAR 23 1973  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name John O. Farmer, Incorporated,  
Complete Address 370 West Wichita Avenue, Russell, Kansas.  
Lease Name McClelland Well No. 5  
Location SE-SE-SE Sec. 2 Twp. 10 Rge. (E) (W) 21  
County Graham Total Depth 4014'  
Abandoned Oil Well        Gas Well        Input Well        SWD Well X D & A         
Other well as hereafter indicated         
Plugging Contractor Above  
Address        License No.         
Operation Completed: Hour 2:00 PM Day 19 Month 3 Year 1973

The above well was plugged as follows:

165'--8 5/8" Surface casing, cement circulated with 100 Sx.  
3832'--5 1/2" casing cemented on bottom. 5 1/2" casing has been squeezed in the Dakota @  
1200'.  
Squeezed 5 1/2" casing initially with 1 sack hulls and 25 Cu. Ft. cement then 30 sacks  
gel to 925' and finally 125 Cu. Ft. cement from 925' to bottom of cellar. Maximum  
pump-in pressure-500#. Final shut-in pressure-200#. Squeezed annulus with 150 Cu.  
Ft. cement from 900' to bottom of cellar. (Mudding and cementing operations by  
Allied Cementing Company, Inc.).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: H. L. D. Johns  
Well Plugging Supervisor

DATE 3-23-73  
INV. NO. 7162-42