



KANSAS CORPORATION COMMISSION 1033962
OIL & GAS CONSERVATION DIVISION

Form CP-1
March 2009

This Form must be Typed
Form must be Signed
All blanks must be Filled

WELL PLUGGING APPLICATION

Please TYPE Form and File ONE Copy

OPERATOR: License #: 5056
Name: Holl, F.G., Company L.L.C.
Address 1: 9431 E CENTRAL STE 100
Address 2: _____
City: WICHITA State: KS Zip: 67206 + 2563
Contact Person: Loveness Mpanje
Phone: (316) 684-8481

API No. 15-185-22969-00-00
If pre 1967, supply original completion date: _____
Spot Description: _____
S2 SE NW Sec. 17 Twp. 21 S. R. 11 East West
2,970 Feet from North / South Line of Section
3,300 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Stafford
Lease Name: KEELER Well #: 3-17

Check One: Oil Well Gas Well OG D&A Cathodic Water Supply Well Other: _____
 SWD Permit #: _____ ENHR Permit #: _____ Gas Storage Permit #: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks
Surface Casing Size: 8.6250 Set at: 278 Cemented with: 225 Sacks
Production Casing Size: 5.50 Set at: 3595 Cemented with: 175 Sacks

List (ALL) Perforations and Bridge Plug Sets:

Attached

Elevation: 1782 (G.L. / K.B.) T.D.: 3600 PBTD: _____ Anhydrite Depth: 540
(Stone Corral Formation)

Condition of Well: Good Poor Junk in Hole Casing Leak at: _____
(Interval)

Proposed Method of Plugging (attach a separate page if additional space is needed):

Heavy mud, hulls, cement and plug according to KCC rules and regulations

Is Well Log attached to this application? Yes No Is ACO-1 filed? Yes No

If ACO-1 not filed, explain why:

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission

Company Representative authorized to supervise plugging operations: Rob Long
Address: 701 E. Santa Fe City: Ellinwood State: KS Zip: 67526 + _____
Phone: (620) 793-0915
Plugging Contractor License #: 31925 Name: Quality Well Service, Inc.
Address 1: 190 US HWY 56 Address 2: _____
City: ELLINWOOD State: KS Zip: 67526 + _____
Phone: (620) 727-3410

Proposed Date of Plugging (if known): _____

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Submitted Electronically

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
DEC 23 2009
KCC WICHITA

DIST 1
RPH

Form	CP1 - Well Plugging Application
Operator	Holl, F.G., Company L.L.C.
Well Name	KEELER 3-17
Doc ID	1033962

Perforations And Bridge Plug Sets

3416	3420	Simpson Sand	
3471	3479	Arbuckle	3460

RECEIVED
DEC 23 2009
KCC WICHITA

STERLING DRILLING COMPANY

BOX 129

STERLING, KANSAS 67579

(316) 278-2131

SAMPLE LOG ----- KEELER #3-17

Located: S/2 SE NW 2260' FNL 2050' FWL, Sec. 17-21S-11W,
Stafford County, Kansas

OWNER: F. G. HOLL COMPANY L.L.C.

ROTARY DRILLING CONTRACTOR: STERLING DRILLING COMPANY

COMMENCED: August 17, 1994

COMPLETED: August 24, 1994

TOTAL DEPTH: 3600' Driller
3595' Logger

LOG

0' - 150' Surface Soil and Sand
150' - 281' Red Bed and Shale
281' - 730' Shale
730' - 3481' Lime and Shale
3481' - 3484' Arbuckle
3484' - 3600' Lime and Shale

RECEIVED
DEC 23 2009
KCC WICHITA

CASING RECORD

Spud at 1:45 PM, 08-17-94. Drilled 280' 12 1/4" hole. Ran 6 joints 8 5/8" casing. 266.58' casing set at 278' K.B. Cemented with 225 sacks 60/40 Pozmix with 2% gel and 3% cc. Plug down at 5:30 PM, by Howco. Good returns. Ticket No. 662200.

Ran 86 joints 5 1/2" 14# new and used casing. 3584.79' pipe set at 3595' K.B. Cemented with 20 BBL of salt flush and 500 gal of Superflush ahead of 50 sacks of Lite cement followed with 125 sacks of F.G. Holl mix. Plug down at 7:30 AM 08-24-94, by Howco. Centralizers on joints 1, 3, 6, 10, and 16. Scratchers 3390'-3440' and 3460'-3510'. Shoe joint 20.16' long. Plugged rathole with 15 sacks.

DEVIATION SURVEY

3/4° @ 280'



Mark Parkinson, Governor
Thomas E. Wright, Chairman
Michael C. Moffet, Commissioner
Joseph F. Harkins, Commissioner

December 23, 2009

Loveness Mpanje
Holl, F.G., Company L.L.C.
9431 E CENTRAL STE 100
WICHITA, KS 67206-2563

Re: Plugging Application
API 15-185-22969-00-00
KEELER 3-17
NW/4 Sec.17-21S-11W
Stafford County, Kansas

Dear Loveness Mpanje:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after June 21, 2010. The CP-1 filing does not bring the above well into compliance with K.A.R 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely,
Production Department Supervisor

cc: District 1

(620) 225-8888

RECEIVED
DEC 23 2009
KCC WICHITA