

15-065-02347-0000

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 18 1966

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Herman George Kaiser, Oil Producer,

Complete Address: 909 Palace Building, Tulsa, Oklahoma.

Lease Name Schneider Well No. B-4

Location NE-SE-SE Sec. 35 Twp. 10 Rge. (E) (W) 21

County Graham Total Depth 3675

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Sun Oil Well Cementing, Inc.,

Address: Box #69, Great Bend, Kansas. License No. _____

Operation Completed: Hour 10:30 AM Day 13 Month 7 Year 1966

The Above well was plugged as follows:

205' -- 8 5/8" Surface pipe, cement circulated with 125 Sx.
3672' -- 5 1/2" Production casing cemented with 135 Sx. Top perforations from
3538' to 3542'. Bridge plug set @ 3490', no perforations above. Dakota
Sands squeezed with 348 Sx. cement.

Ran float to check hole for fluid, found top of fluid @ 450'. Pumped in
67 sacks cement. Final shut-in pressure 2000# on 5 1/2". Checked anulus
between 5 1/2" and surface with 200# water pressure. Held for 15 minutes.

(Cementing operations performed by Sun Oil Well Cementing, Inc.,)

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 7/18/66
INV. NO. 3576-u