

15-163-12278-0000

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 13 1973  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Westrans Petroleum, Inc.

Complete Address P. O. Box 693 Great Bend, Kansas 67530

Lease Name Leben-Sutor "A" Well No. 11

Location NE NW SE Sec. 24 Twp. 10 Rge. (E) (W) 20

County Rooks Total Depth 3759'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Knight Casing Pulling Co.

Address Box 405 Chase, Kansas 67524 License No. 436'

Operation Completed: Hour 12 N Day 10 Month 2 Year 1973

The above well was plugged as follows:

Total Depth 3759' 8 5/8 csg set at 164' cwc: 140 sk.

5 1/2 csg set at 3757' cw 100 sk cmt.

Dakato squeezed. Cutoff and recovered 412' of 5 1/2 csg.

Pumped down 8 5/8 csg with 50 sk cmt --25 sk gel & water W/400 lbs hulls --50 sk

cmt --10 sk gel & water --released 8 5/8 plug and pumped 50 sk cmt by "Allied."

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Boz. Massey  
Well Plugging Supervisor

DATE 2/14/73  
INV. NO. 6972-4