

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 56-26

LOCATION SE SE SW

SEC. 24 TWP. 10 RGE. 20W

Dry Hole x Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Earl

Operator Nadel & Gussman Address 1714 1st Natl Tulsa, Okla

Field _____ County Rooks

Total Depth 3745 Feet.

Plugging Contractor Barnes & Sons

Plugging Contractor's License No. 9

Address _____

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 166' circulated with cement - 5 1/2" at 3738' with

12s sax cement behind - Baker plus to 3690' - perforated

at 3626'.

Filled with sand to 3610', set 4 sax cement with dump bailer,

pulled 2710' 5 1/2" - filled with mud to 165', set rock and 15

sax cement, mud to 35', set rock and 10 sax cement to bottom

cellar.

Edson Perry

District Conservation Agent

Date 5-3-56

STATE CORPORATION COMMISSION

MAY 11 1956

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 24 T 10 R 20W
BOOK PAGE 56 LINE 26