

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 29 1974

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Southern States Oil Corporation

Complete Address Box 693, Great Bend, Kansas 67530

Lease Name Sutor "A" Well No. 6

Location SW SE NE Sec. 24 Twp. 10 Rge. (E) (W) 20

County Rooks Total Depth 3790'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling

Address Box 405, Chase, Kansas 67524 License No. 436

Operation Completed: Hour 11 A Day 26 Month 7 Year 1974

The above well was plugged as follows:

Total Depth 3790' 8 5/8 csg set at 187' cwc 100 sk.

5 1/2 csg set at 3788 1/2 cw 100 sk.

Filled 5 1/2 csg W/sd (3790'-3750') dumped 5 sk cmt W/dump bailer. (3750-3715)

5 1/2 csg squeezed @ 1312' W/75 sk cm. & 1240' W/129 sk cm. Recovered 600' of 5 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel & water W/100 lbs hulls -released 8 5/8 plug & pumped 100 sk cement.

I hereby certify that the above well was plugged as herein stated.

Signed: Ben F. Massey
Well Plugging Supervisor

INVOICED

DATE 7/29/74

INV. NO. 9617-W