

15-163-02348-0000

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUL 29 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Southern States Oil Company

Complete Address P. O. Box 693, Great Bend, Kansas 67530

Lease Name Sutor "A" Well No. 5

Location NE SW NE Sec. 24 Twp. 10 Rge. (E) (W) 20

County Rooks Total Depth 3759'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling

Address Box 405, Chase, Kansas 67524 License No. 436

Operation Completed: Hour 4 P Day 26 Month 7 Year 1974

The above well was plugged as follows:

Total Depth 3759' 8 5/8 csg set at 183' cwc 125 sk.

5 1/2 csg set at 3757' cw 100 sk cmt.

5 1/2 csg PBTB 3640' -sand back to 3600' -dumped 4 sk cmt W/dump bailer.

5 1/2 csg squeezed at 1034'-1094' W/125 sx cem. & @ 1061' W/200 sk cem. No pipe recovered.

Recovered 480' of 5 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel & water W/200 lbs hulls -released 8 5/8 plug

& pumped 100 sk cem.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo A. Massey
Well Plugging Supervisor

INVOICED

DATE 7/29/74

INV. NO. 9616-W