

15-163-19018-0000

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUL 25 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Southern States Oil Co.

Complete Address Box Box 693 Great Bend, Kansas 67530

Lease Name Sutor "A" Well No. 3

Location NE NW NE Sec. 24 Twp. 10 Rge. (E) (W) 20

County Rooks Total Depth 3759'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling

Address Box 405, Chase, Kansas 67524 License No. 436

Operation Completed: Hour 11:30 A Day 24 Month 7 Year 1974

The above well was plugged as follows:

Total Depth 3759' 8 5/8 csg set at 193' cwc 160 sk.

5 1/2 csg set at 3759' cw 175 sk.

Filled 5 1/2 csg W/sd (3759-3740) dumped 5 sk cmt W/dump bailer. (3740-3705)

5 1/2 csg sq. @ 940' W/100 sx cem. Recov. 490' of 5 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel & water W/100 lbs hulls, released 8 5/8 plug & pumped 100 sk cem.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Massey
Well Plugging Supervisor

INVOICED

DATE 7/29/74

INV. NO. 9599-W