

15-163-02187-0000

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUL 29 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Southern States Oil Company
Complete Address P. O. Box 693, Great Bend, Kansas 67530
Lease Name Sutor "A" Well No. 1
Location NE SE NE Sec. 24 Twp. 10 Rge. (E) (W) 20
County Rooks Total Depth 3760'
Abandoned Oil Well XX Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Knight Casing Pulling
Address Box 405 Chase, Kansas 67524 License No. 436
Operation Completed: Hour 1 A Day 26 Month 7 Year 1974

The above well was plugged as follows:

Total Depth 3760' 8 5/8 csg set at 248' cwc 150 sx.
5 1/2 csg set at 3759' cw 85 sk cmt.
Filled 5 1/2 csg W/sd (3760-3740) dumped 5 sk cmt W/dump bailer. (3740-3700)
5 1/2 csg squeezed @ 1010' W/100 sk cem. & 710' W/100 sk. Recovered 511' of 5 1/2 csg.
Pumped down 8 5/8 csg with 20 sk gel & water W/100 lbs hulls, -released 8 5/8 plug
& pumped 100 sk cement.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Massey
Well Plugging Supervisor

INVOICED

DATE 7/29/74
INV. NO. 9615-W